

BID FORM

Bidder Information:

Name of Company: _____

Address: _____

Signing Authority
and Title: _____

Email: _____

Phone: _____

Signature: _____

Date: _____

ADDENDA

The Bidder hereby acknowledges and agrees that the following addenda below form part of the Bid Document and has carefully examined the addenda having included all aspects thereof in their Bid:

Addendum Number	Date	Received by Bidder (✓)

*If no Addenda have been issued then this table may be left blank

SUBCONTRACTORS

The following is a list of Subcontractors proposed to be used. Any changes or additions to the subcontractors to be utilized must be approved in writing by the Owner prior to any work being performed by that Subcontractor.

Scope of Work	Subcontractor Name and Contact	Phone Number	Email

PROPOSED ALTERNATIVES TO WORK

It is mandatory for the Bidder to submit a price for the work as specified.

Should the Bidder not agree with the materials or methods specified in the Tender Documents, they shall notify the Contract Administrator, in writing, stating their reason for objection and may submit a suggested alternative. In such an event, the Contract Administrator may choose to issue an addendum.

REFERENCES

The Bidder shall provide three (3) references for work similar in scope as described in this Tender.

Year Completed	Desc. of Work	Company and Contact Name	Phone Number	Email

SCHEDULE OF PRICES

The Bidder shall note the following abbreviations/acronyms.

Abbreviation/Acronym	Description
m	= Linear metre
m ²	= Square metre
m ³	= Cubic metre (compacted)
LS	= Lump Sum
ea.	= each
t	= Tonnes (2,204.6 lbs)
hrs	= hours
CB	= Catchbasin
DICB	= Ditch Inlet Catchbasin
JB	= Junction Box
c/w	= Complete with
ROW	= Right of Way

This schedule must be completed in full and attached to the form of Tender.

Tender Bid Form**Richardson Drain**

Item No.	SP No.*	Description	Approx. Quantity	Unit Price	Total
A1	1	Pre-construction meeting, mobilization, de-mobilization.	LS		\$
A2	2	Supply 19mm (¾") clear crushed stone.	180 tonne	\$	\$
A3	3	Supply 150mm to 300mm dia. rip-rap and required geotextile underlay.	40 tonne	\$	\$
A4	4	Tree clearing, grubbing, and brushing as specified.	LS		\$
A5	5	Construct a temporary rock check dam (OPSD 219.211) c/w removal once construction area has stabilized (Sta. -0+003).	LS		\$
A6	6	a) Excavation of stilling basin c/w placement of rip-rap per the accompanying details, not including the supply of rip-rap (Sta. -0+003 to 0+000).	LS		\$
		b) Hand seeding of disturbed and exposed channel banks and work area as specified.	LS		\$
A7	7	a) Supply 525mm dia. solid, split coupler, HPDE pipe (320 kPa) c/w required couplers and rodent grate.	6 m	\$	\$
		b) Install HDPE outlet pipe and rodent grate (Sta. 0+000 to 0+006).	LS		\$
A8	7	a) Supply 525mm dia. concrete tile (2000D) and required geotextile.	109 m	\$	\$
		b) Locate and destroy existing drains.	LS		\$
		c) Install concrete tile via wheel trencher (Sta. 0+006 to 0+115).	109 m	\$	\$
A9	7	a) Supply 450mm dia. concrete tile (2000D) and required geotextile.	468 m	\$	\$
		b) Locate and destroy existing drains (Sta. 0+115 to 0+583).	LS		\$
		c) Install concrete tile via wheel trencher (Sta. 0+115 to 0+472).	357 m	\$	\$
		d) Supply one 45 degree, 450mm dia. HDPE elbow (320 kPa) with plain ends and required geotextile (Sta. 0+535).	LS		\$
		e) Install concrete tile via excavator on 19mm clear stone bedding c/w the installation of elbows and crossing the private water service (Sta. 0+472 to 0+583).	111 m	\$	\$

*SP No. refers to the Special Provisions - Project Specific Construction Specification Associated with the Item

Item No.	SP No.*	Description	Approx. Quantity	Unit Price	Total
A10	7	a) Supply 450mm dia. solid, split coupler, HPDE pipe (320 kPa) and required couplers.	18 m	\$	\$
		b) Hand seeding of disturbed vegetated areas.	LS		\$
		c) Install HDPE pipe drain crossing and culvert through private laneway via excavator on 19mm clear stone bedding as per accompanying detail c/w the destruction of the existing drains, removal and disposal of existing culverts and restoration of laneway as specified (Sta. 0+583 to 0+592).	18 m	\$	\$
A11	8	a) Supply 600mm x 600mm concrete DICB c/w birdcage grate, tabs, and marker.	LS		\$
		b) Install DICB (Sta. 0+592).	LS		\$
A12	7	a) Supply 450mm dia. concrete tile (2000D) and required geotextile.	86 m	\$	\$
		b) Supply two 45 degree, 450mm dia. HDPE elbows (320 kPa) with plain ends and required geotextile (Sta. 0+595 and 0+678).	LS		\$
		c) Locate and destroy existing drains.	LS		\$
		d) Install concrete tile via excavator on 19mm clear stone bedding c/w the installation of elbows and regrading of existing channel and surrounding area as specified (Sta. 0+592 to 0+678).	86 m	\$	\$
Old Stage Road					
A13	8	a) Supply 600mm x 600mm concrete DICB c/w birdcage grate, tabs, and marker.	LS		\$
		b) Install DICB (Sta. 0+678).	LS		\$
A14	9	a) Supply 450mm dia. solid, split coupler, HPDE pipe (320 kPa), required couplers, and required Granular 'A'.	33 m	\$	\$
		b) Hand seeding of disturbed vegetated areas.	LS		\$
		c) Install HDPE pipe drain crossing and culvert through Old Stage Road via excavator as specified c/w the destruction of the existing drains, removal and disposal of existing culvert and restoration of road (Sta. 0+678 to 0+696).	33 m	\$	\$
A15	8	a) Supply 600mm x 600mm concrete CB c/w birdcage grate, tabs, and marker.	LS		\$
		b) Remove and dispose of existing CB.	LS		\$
		c) Install CB (Sta. 0+696).	LS		\$
		d) Supply and install approx. 6m of 300mm dia. solid, ag tubing and required fittings for connection of existing tiles to CB.	LS		\$
SUBTOTAL - Richardson Drain					\$

*SP No. refers to the Special Provisions - Project Specific Construction Specification Associated with the Item

Provisional Items

These costs are included to account for construction activities that may or may not be required at the time of construction.

Item No.	SP No.*	Description	Approx. Quantity	Unit Price	Total
P1	10	Removal of wheel trencher due to stony conditions.	5 ea.	\$	\$
P2	11	Increased cost to install drain on 19mm (¾") clear stone bedding in areas of soil instability as per detail Typical Drain Installation on Stone Bedding, not including the supply of clear stone.	150 m	\$	\$
P3	12	Tile connections into the proposed drain with core drilled hole and coupler.			
		a) 100mm dia. connection.	5 ea.	\$	\$
		b) 150mm dia. connection.	2 ea.	\$	\$
P4	13	Supply and install Granular 'B' material	50 tonne	\$	\$
SUBTOTAL - Provisional Items					\$

TOTAL BID (Including Prov. Items)	\$
HST (13%)	\$
TOTAL (INCLUDING HST)	\$

Note: All prices are in Canadian Dollars

WORK SCHEDULE

Proposed Start Date:	
Proposed Completion Date:	

*SP No. refers to the Special Provisions - Project Specific Construction Specification Associated with the Item